
Appendix E

Waste Removal (manure) Plan

DIXON DOWNS MANURE MANAGEMENT PLAN

Manure Management Plan

1. Horse stalls will be cleaned of horse manure and bedding waste (“Horse Waste”) on a daily basis.
2. Horse waste will be taken from each stall and placed in containers (“Barn Containers”) located in a designated area at the end of each barn.
3. Each Barn Container will have a lid which will be closed except when waste is placed in or removed from container or when container is cleaned.
4. Only horse waste will be placed in the Barn Containers. The Barn Containers will be easily identifiable.
5. The Barn Containers will be transported on a daily basis from the barn area to the Manure Transfer Building for temporary storage until removal with the next 24 hours.
6. The Manure Transfer Building will have a roof over the building including the truck transfer area to prevent rain water from mixing with the Horse Waste.
7. The Manure Transfer Building will have an impervious floor surface.
8. Horse Waste from the Manure Transfer Building will be loaded onto transport trucks and removed on a daily basis to approved locations.
9. Records will be maintained onsite of the estimated quantity of Horse Waste transported from the Dixon Downs facility each day.

